



# High Commission of India Colombo

## CORRIGENDUM



Reference Tender No. Col/DC/228/3/2011 dated 02 August 2015 for Construction of Rabindranath Tagore Memorial Auditorium at University of Ruhuna.

Bidders may note the following changes in the Tender documents:

### **Bill of Quantities:**

No	Item No	Revision
1	1A/15	Allow lump sum for employing suitably qualified and experienced technical personnel on part time basis for Construction Management Services at the site.
2	1A/41	Item description to be corrected as "Allow lump sum for stamp duty in accordance with the prevailing regulations of the Government. CIGF leavy 1%"
3	2D/13	Unit to be changed as Provisional Sum-SLR.500,000.00
4	2H/09 & 2H/10	Description to be amended as "Width $\leq$ 300 mm vertical, work subsequently covered"
5	2L/14	Description to be corrected as "Door type FD1, size 1500 x 2400mm, Local Teak timber door with timber frame as per detail drawing and thickness as 60mm".
6	2L/15	Description to be corrected as "Door type FD2, size 900 x 2100mm, Local Teak timber fire door (with 120 minutes fire protection) with solid local teak timber frame. Panic bolt should be fixed at inside and lock with handle should be fixed at outside. All locks, handle, hinges and accessories should be rust resistance / rust free, no corrosion acceptable as per detail drawing and thickness as 60mm."
7	2L/33	"13mm thick planks" to be included
8	2L/34	"25mm thick planks" to be included
9	2Q/42	"Urinal flush valve is manual" to be included
10	2Q/47	Quantity to be changed as "14"
11	2Q/48	Description to be corrected as "Supply and installation of 4mm thick Mirror size 2100x750mm high; bewelled edge to match above fittings". Quantity to be corrected as 2 nr
12	2Q/49	Item to be deleted
13	2T/04 to 2T/24	A Concrete finish in which the small aggregate – either typical washed/ gravel/ concrete chip is exposed by removal of the cement and fine aggregate from the surface of the concrete by brushing or pressure washing before the cement has set after the concrete has cured.
14	2T/34, 2T/35 &	Prime cost for Granite tile is SLR 15,000.00 per m2

	2T/36	
15		Grand summary page to be replaced with Annexure-A
16	3E (A/C and ventilation)	Detailed specification is given as Annexure-B

**Fire system :**

- Bidders can quote equivalent product for fire system having minimum certification of LPCB, UL listed & FM approved. Country of origin should be Europe, USA & Canada.
- Welded joints are applicable

**Prime Cost:** Prime cost includes cost of all accessories, transportation and related expenses

**Drawings:**

No	Item No	Remarks
1	Timber Facia – Item No 2L/35, 2L/36	Details already provided in the drawings
	Wall Panel at Auditorium - Item No 2L/39	
	Timber framework for Asbestos free ceiling - Item No 2N/03	
	Decorative Isolated column - Item No 2T/31	
	Decorative Isolated moulding - Item No 2T/32	
	Granite counter top - Item No 2T/34, 2T/35 & 2T/36.	
	Cement finished counter top - Item No 2T/37	
	Expansion joint - Item No 2F/34	
	Septic Tank & Soakage Pit – 2W/22 & 2W/23	
	Solid Timber Furniture – 3C/03 & 3C/04	
	Detail drawings for AC & Fire	
2	Additional drawings are attached at Annexure-C	

**Note:**

**Invitation for Bid clause No 8 & Bidding Data: Clause No 25.1:**

Bidders may note that the last date for submission of bids has been extended till 1500 hrs on 15 September 2015 and the technical bids will be opened on the same day at 1530 hrs

**All other terms & conditions of the tender will remain unchanged. This Corrigendum will be part of the tender document.**

