



Government of India

High Commission of India
Colombo

CORRIGENDUM



Reference Tender No. Col/Com/228/8/2011-A dated 24 March 2013 for Construction of Centre for Skill Development for the Faculty of Engineering at Ariviyal Nagar, Kilinochchi

Bidders may note the following changes in the Tender documents:

1. Contract Data

1.1.3.3 Time of completion is 15 months

14.2(b) Advance recovery: Advance recovery shall be from first four interim bills equally.

14.5 Minimum amount of Interim Payment Certificate is SLR 30,000,000/-

2. General Note

D CONCRETE WORK

Concrete

Cement shall be SLS approved according to the manufacturers' specification and to the approval of the consultant.

To be read as:-

Unless otherwise stated all concrete work shall be

- a. 1:1 1/2:3 (3/4") or Grade 30 which ever is higher below ground and 1:2:4 (3/4") or Grade 25 which ever is higher above ground.
- b. Blinding beds shall be 1:3:6 (3/4 ") or Grade 15 which ever is higher.

To be added:-

Cube test to be carried out and submitted by the contractor at his own cost.

Rates shall include for :-

To be added:-

Casting and testing cubes.

Reinforcements

To be added:-

Steel shall comply to B.S Specification

Rates shall include for :-

To be added:-

For testing samples in random selected at site.

G **Finishes****Tiling****To be added:-**

200mm x 300mm floor tile approximately Rs.150/= per sq.ft

N **Electrical Installation****Delete** (c) Fans - Usha , KDK / Japanese - National / UK- GEC**Add as** © Fans are to be of the best quality and to be purchased from an Authorized dealer, The minimum base price should be Rs. 6750/=

The approval to be obtained from the consultant.

H **ALUMINIUM WORKS****To be read as:-**

C. All necessary iron monger and locking devices using DORMA - of Japan origin fittings or equivalent.

J **ROOF WORKS****To be read as:-**

All roof works shall conform with the British Standards 9869:1972 or Indian Standards 1252;1975. Thickness of coated roofing sheets shall not be less than 0.47mm.

K **SAINTARY PLUMBING****To be read as:-**

Chrome plated angle valves to be provided as required, Brass gate valves to be provided as required and to be approved by the Architect.

Addendum-1

Bill of Quantities for the Proposed Civil and Mechanical Engineering Block(CME), Faculty of Engineering, University of Jaffna At Ariviya Nagar, Kilinochchi.

Item	Description	Units	Qty.	Rates	Amount
A	<u>PRELIMINARIES</u>				
	To be read as:-				
A-5	Allow provision for temporary electricity during the project (Consumption to be paid to Ceylon Electricity Board)	Item	Allow	Sum	
D	Concrete				
	Answers to the questions raised at pre bid meeting.				
	To be read as:-				
	Reinforcement				
D22	6mm and 10mm for stirrups	kg	14,150.00		
D25	Column shaft up to first floor slab	kg	24,600.00		

D26	Column shaft from first floor to second floor	kg	23,900.00		
D29	Slab and beam at first floor.	kg	53,875.00		
E	<u>BLOCK WORK</u>				
E1	6" thick solid block work in cement and sand 1:5 in the ground floor as per detail drawing.	Sq	145.00		
G	<u>FINISHES</u> Refer Addendum -1, General Notes, G-Finishes for G-25 to G-27				
	To be added as:-				
G38	Mastic Asphalt fill along the slab and beam to the depth	L.ft	500		
H	Aluminium Works Answers to the questions raised at pre bid meeting. Drawings attached				

Item	Description	Units	Qty.	Rates	Amount
<u>J</u>	ROOF WORKS To be read as:-				
J9	Supplying and installing barge board 0.47 gauge zinc alum with necessary bracket out of 1/8"G.I flat iron as per drawing.	L.ft	880.00		
	To be deleted and read as:-				
J11	5/8" thick Mineral fiber ceiling 2'-0"X2'-0" with adjustable hook on powder coated G.I frame in slope along the roof underneath	Sq	190.00		
	To be read as:-				
J12	5/8" thick Mineral fiber flat ceiling 2'-0"X2'-0" with adjustable hook on powder coated G.I frame.	Sq	16.00		
<u>K</u>	<u>SANITARY AND PLUMBING</u> To be added as:-				
K5	Preassure testing the supply lines	Item	Sum		
	To be read as:-				

	<u>Sanitary Fixtures and Fittings</u>				
K7	Mirror above wash basin comprising plate glass mirror free from effect of wavy image , approved hard wood back 0'-3/4" thick , water based finish, chromium plated clips and lugs fixed to wall with fiber plugs and chromium plated brass screws. Sizes of mirror 4'-0" x 2'-0"	No	8.00		
K11	Chromium plated / white / colored(origin china)Supplying and fixing soap tray (Origin- China)	No	39.00		
K12	Chromium plated / white / colored(origin china)Supplying and fixing towel rail (Origin- China)	No	39.00		
N	<u>Electrical Installation</u>				
	To be read as:-				
N1	Supplying and laying wiring for lamp point.	No	620.00		
N27	Termination of cable with necessary lugs from MDB SMDB and DBS	Item	Sum		
N	<u>Carpentary & Joinary</u>				
	Answers to the questions raised at pre bid meeting. Drawings attached				

All other terms & conditions of the tender will remain unchanged. This corrigendum Notice will be a part & parcel of the tender.